BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT40938

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/28/2019-20, Date: 17.03.2020

Name of Work:Maintenance of Cremitorium Burial Ground in ward no 5 Jakkur

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PRAVEEN B S ( )	
				In Figures	In Words
1	57	KSRB 2-2.1:: Earthwork excavation for foundationof buildings, water supply and sanitary lines and electrical conduitsetc, either in pits or in trenches 1.5m and above in width, in soil notexceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications.. No. KBS 2.1(b) / 2.3.5 (pg no.6, I/No2.4,)	Cum	301.39	Rupees Three Hundred One and Thirty Nine Paise Only
2	5.7	KSRB 4-1.2 : Providing and laying in position plain cement concreteof Mix 1:4:8 with OPC @ 220kgs, with 40mm and down size gradedgranite metal coarse aggregates @0.892cum and fine aggregates @0.465cum machine mixed, machine mixed, concrete laid in layers notexceeding 15 cms. thick, well compacted, in foundation, including costof all materials, labour, HOM curing complete as per specifications.Specification No. KBS 4.1, 4.2 (pg No.13.I.No.4.2)	Cum	5331.29	Rupees Five Thousand Three Hundred Thirty One and Twenty Nine Paise Only
3	27	KSRB 5.2-3 : - Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 (P.No.25- I.No.5.6)	Sqm	4717.48	Rupees Four Thousand Seven Hundred Seventeen and Forty Eight Paise Only
4	36	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. No. KBS 4.6.2 (P.No.16 - I.No.4.31)	Sqm	367.46	Rupees Three Hundred Sixty Seven and Forty Six Paise Only
5	11.88	KSRB 4-6.5 : Providing and removing centering, shuttering, strutting,propping etc., and removal of form work for columns, pillars, postand struts, square / rectangular/ polygon in plan including cost of allmaterials, labour complete as per specifications.Specification No. KBS 4.6.2 (P.No.16 - I.No.4.32)	Sqm	468.05	Rupees Four Hundred Sixty Eight and Five Paise Only
6	6.92	KSRB 4.2.1 : Providing and laying in position reinforced cement concrete of Design Mix M25 with OPC @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70 cum and fine aggregtes @ 0.47cum, with super plasticisers @ 3 liters confirming to IS 9103-1999 reafirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters,columns, pillars,posts,struts,buttresses,bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM curing, complete but excluding cost of reinforcement as per specifications.(P.No.14- I.No.4.10)	Cum	5965.62	Rupees Five Thousand Nine Hundred Sixty Five and Sixty Two Paise Only
7	0.76	KSRB M2200-6 Providing T.M.T bars Fe 550 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. MORTH Specification NO.1600&2200 (Pg No.229 Item No.28.8.3)	Tonne	70630.84	Rupees Seventy Thousand Six Hundred Thirty and Eighty Four Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PRAVEEN B S ( )	
				In Figures	In Words
8	108	KSRB 5-14: Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. blocks of size 400x200x200mm KBS No.5.4 (P.No-27,I No-5.26.1)	Sqm	914.28	Rupees Nine Hundred Fourteen and Twenty Eight Paise Only
9	10.5	Providing and fixing M.S. Gate as per Chief Architect Drawing, using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16 x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmx6mm M.S. flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc., complete. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, with lead and lift, loading and unloading charges, etc., complete as per specification. (P.No-45,I No-7.37)	Sqm	3091.61	Rupees Three Thousand Ninety One and Sixty One Paise Only
10	21	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. (P.No-123,I No-15.74)	Sqm	97.51	Rupees Ninety Seven and Fifty One Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92